

DNIT of special repairing in Central Bank of India of A.I. Jat H.M. College, Rohtak

Sr. No.	Description of Item	Quantity	Rate	Premium	Rate with Premium	Amount
1.	Reinforced C.C. with cleaning & straightening & cutting of bars if required HSR – 8.6 (E)	1.00cum	108.05	550%	702.32	
2.	Dismantling Brick work in cement HSR-8.5 (B)	12.29cum	35.60	550%	231.40	
3.	Removing Doors & windows with chocket by making recess in walls when the wall is not to be dismantled HSR-18.18 (a & c)	5 nos. 6 nos.	11.90 7.55	550% 550%	77.35 49.07	
4.	1 st Class brick work in cement sand mortar 1:6 in foundation & plinth HSR-11.2	2.39 cum	393.45	600%	2754.15	
5.	C.C. 1:8:16 with Brick ballast 40mm nominal size in foundation & plinth HSR-10.26	1.10cum	300.20	450%	1350.90	
6.	Excavation in earth work for trenches & walls as per HSR-6.6	1.56 cum	1108.10/100 cum	425%	5817.53	
7.	C.C. 1:2:4 with stone agg. 20mm nominal size in foundation & plinth HSR-10.41	0.51 cum	615.60	450%	3385.80	

8.	Tor steel for RCC work for slab & beams where not C.C. is not including but steel rate is given complete. HSR-18.22	1.20 quintal	917.05	500%	5502.30	
9.	C.C. 1:1.5:3 with stone agg. 20mm nominal size in RCC slab including complete rate of C.C. & excluding rate of steel. HSR-10.82+10.95a	1.00cum	1084.80	450%	5966.40	
10.	Providing & fixing antiskid tiles of size 400X400mm or above size of approved make in flooring in any pattern as specified over base of 20mm thick cements sand mortar 1:3 & jointed with white cement slurry mixed with pigment. HSR-14.91. Paid as per actual work	3.89sqm.	624.00	-15%	530.40	
11.	P/F glazed wall tiles of size 200X300mm in all colors and shades. HSR-14.92 (a)	71.86sqm.	501.75	NIL	501.75	
12.	P/F in position laboratory suit (White) HSR-30.42 (ii) 480X400mm	3	359.00	340%	1579.60	
13.	P/F in position stain less steel sinks with complete fitting. HSR-30.53 (a) 600X450X200mm	1	5386.00	30%	7001.80	
14.	12mm thick C.P. 1:4 on walls as per HSR-15.5. Paid as per actual work	50sqm.	12.70	500%	76.20	
15.	10mm thick C.P. 1:4 under ceiling as per HSR-15.52. Paid as per actual work	50sqm.	12.65	500%	75.90	

16.	Distempering with OBD with two coats on old distempered work H.S.R. 16.60	400sqm.	6.00	230%	19.80	
17.	Providing two coats of exterior acrylic emulsion paint. H.S.R. 16.79 (b) 1 st quality	250sqm.	48.75	NIL	48.75	
18.	P/F best Indian make Indian type Orissa water closet suit in floor. H.S.R. 30.2 (a) white 580mm	1			4070.00	
19.	P.F. vitrified tiles of size 600X600mm laid in any pattern in cements sand mortar 1:3 & jointed with jointed filler of same color. HSR-14.89. Paid as per actual work	81.80sqm.	924.30	-15%	785.65	
20.	Provision for sewer line from R/W/P gully trap to main hole on old line I/C required chambers etc. complete. Paid as per actual					
21.	Provision for Marble Stone Baroda Green on slab top complete as per HSR-14.52 C (i)	3sqm.	779.00	90%	1480.10	
22.	Wrought Iron or mild steel ladders grills window guards iron doors & any other type of railing including cost of screws & welding roads as per HSR-18.12	2 Quintal	1040.35	500%	6242.10	

Note:- N.S. items if required at the time of execution will be paid on analysis rate on the basis of current market rate.