

**Renovation of Tiolet, Sainitory Fitting, Glazed Wall & Flooring Tiles & Other concerned item in Seth Chhaju Ram Boys Hostel  
A.I. Jat H.M. College, Rohtak**

Sr. NO.	Discription of Item	Sr. No. of HSR	Quantity	UNIT	Rate	C.P.	Complete Rate for C.P.	Amount
1	Dismantling cement conglomerate/terazzo-floors 25mm to 50mm thick including concrete base	8.25	331.64	sqm.	5.75	550%	37.37	12,393/-
2	Dismantling cement conglomerate/terazzo-floors 25mm to 50mm thick without concrete base	8.26	460.41	sqm.	3.05	550%	19.82	9128/-
3	Pvdg & fixing ceramic tiles/anti skid tiles of size 400mm x 400mm or above size of approved make in flooring, laid in any pattern as specified over base of 20mm thick cement coarse sand mortar 1:3 and jointed with white cement slurry mixed with pigment to match the shade of tiles. Note: Tiles shall be of premium quality (first quality) of reputed manufacturer like NITCO, KAJA-RIA, SOMANI, ORIENT & JOHNSONS.	14.91	331.64	sqm.	624	-15%	530.4	1,75,902/-
4	Providing and fixing Ist quality ceramic glazed wall tiles confirming to I.S. 15622 (thickness to be specified by the manu-facturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-In-Charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 coarse and jointed with grey cement mixed with pigment of matching shades complete	14.92	460.41	sqm.	648.15	NIL	648.15	2,98,415/-
5	Providing and fixing in position best Indian make (to the approval of the Engineer-in-charge). Indian type orissa or orya water closet suite for sinking into floor, with raised foot treads complete with 100mm H.C.I. 'P' trap with or without vent as required and all other necessary fitting as fully descried in item No. 30.1 above. (a) Size 580mm (i) White	30.2 (a)	2	Each	925	340%	4070	8140/-

6	Providing and fixing in position best Indian make (as approved by the Engineer-in-charge) European type water closed suit with non-concealed 'P' or 's' trap with or without vent and all toher necessary fittings as fully described in item No. 30.3 above. (i) White	30.4	2	Each	901	340%	3964.4	7929/-
7	Extra over item Nos. 30.3 to 30.6 for providing and fixing best Indian make plastic hygenic seat with lid complete instead of hollow black or white plastic seat and lid (i) White plastic seat (Solid)	30.13	2	Each	193	340%	849.2	1698
8	Providing and fixing in position 15mm i/d C.P. brass bib cocks of best quality (as required by the Engineer-in-charge) (a) Bib cock lon body © Bib cock	30.75	4 4	Each	116 100	340%	510.40 440	2042/- 1760/-
9	Providing and fixing in position C.P. brass stop cocks (as approved by the Engineer-in-charge). (a) 15mm stop cock. (i) Stop cock male & female	30.76	20	Each	101	340%	444.4	8,888/-
10	Providing and fixing in position best Indian makeek a range of three urinals large flat back or angular lipped front 610mm high in vitreous chinaware with one No. 10 liters capacity best Indian make C.I. automatic flushing cistern with fittings and flush pipe etc. complete as fully described in Item No. 30.25 above. (i) White	30.27	1	Each	2679	340%	11787.6	11788/-
11	Extra over item No. 30.1 to 30.4 and 30.6 for providing and fixing 15 liters capacity low level vitreous china ware cistern complete with flush bend all other necessary fitting instead of C.I. high level cistern complete with fittings. (i) White	30.12	15	Each	290	340%	1276	19140/-

12	Factory manufactured solid flush door shutters, with block board core as per I.S. No. 1659-1669 bonded with water proof type phenol formaldehyde synthetic resin, hotpressed, conforming to I.S. 2202 part I and II, fixed in position, including iron hinges, screws, chocks/cleats and stops etc. (excluding the cost of any fittings other than specified above, but including labour for fixing the same in position)- (iii) 35 mm thick	17.93	16	Each	448	165%	739.2	11,827/-
13	Providing and fixing 0.50mm thick aluminium sheet including cost of necessary screws, etc., complete	17.87	16	Each	90.35	300%	362.2	4307/-
14	Providing and fixing in position best Indian make bevelled edge 5.5 mm thick mirror mounted on asbestos sheet ground fixed in position by means of 4 Nos. chromium plated brass screws and washers over rubber washers and rawl plug embedded in the wall or chromium plated brass clamps with C.P. brass screws (as required by the Engineer-in-charge) complete including cutting and making good the walls etc. (a) Indian make (i) 600mm X 450mm	30.71	4	Each	107	340%	470.8	1883
15	Providing and fixing in position best Indian make PVC connection with washer etc. complete in all respect (600 mm) long	NS	20	Each	250			5000/-
16	Providing and fixing in position best Indian make CP brass waste pipe jali complete in all respect	NS	15	Each	50			750/-
							Total	5,80,990/-
							ADD Escalation @ 10%	58,099/-
							<b>Total</b>	<b>6,39,089/-</b>
							<b>Say Rs.</b>	<b>6,40,000/-</b>