

Detail Notice Inviting Tender

Name of work - Repair of Auditorium Hall

Estimated Cost - Rs. 2850195-00

Earnest Money - Rs. 57004-00

SR. No.	H.S.R. Item No.	Description	Unite	Quantity	H.S.R. Rate 1988	Contractor Rate
1	8.25	Dismantling Flooring and Ceiling Dismantling cement conglmerate / terrazzo floors 25 mm to 50 mm thick including concrete base	Sq.m.	990.856	5.75	
2	8.32 .(c)	Scraping cement plaster	Sq.m.	1500.000	1.90	
3	8.18 (a)	Removing door and windows (wood and steel) with chowkats by making recesses in walls when the walls is not to be dismantled doors	Nos.	12.000	11.90	
4	14.1	Base course of floors consisting of 100 mm thick cement 1:8:16 and 100 mm sand or stone filling.	Sq.m.	744.994	36.95	
5	14.4	Screed of 50 mm thick cement concrete 1:8:16 to be laid below the topping.	Sq.m.	247.727	15.35	
6	14.62	Kotah Stone Flooring, Wail Lining and Dado Kotah stone flooring 34 mm to 40 mm thick in any pattern as specified over 12 mm thick base of cement coarse sand mortar 1:3 laid and jointed with neat cement slurry mixed with pigment to match the shade of stone including rubbing and polishing.	Sq.m.	990.856	201.95	
7	15.4	Plastering on walls 12 mm thick cement plaster 1:3	Sq.m.	1500.000	15.00	

8	17.93(a)i	Factory manufactured solid flush door shutters, with block board core as per I.S.No.1659-1969 bonded with water proof type phenol formaldehyde synthetic resin,hotpressed,conforming to I.S.2202 part I and II, fixed in position,including iron hinges,screws,chocks/cleats and stops etc.(excluding the cost of any fittings other than specified above,but including labour for fixing the same in position)- (a) commercial veneering with vertical grains or cross bands and face veneer on both sides commercial facing with laminated core and lipped edges.) (i) 25 mm thick	Sq.m.	37.346	399.00	
9	34.13	Providing & laying strip seal expansion joint catering to maximum horizontal movement upto 70mm, complete as per MORT & H specification no. 2607 to be installed by the manufacture/ supplier or their authorized representative ensuring compliance to the manufacture's instructions for installation.	Sq.m.	562.966	8000.00	
10	13.93	Providing & fixing False Ceiling with grooves with 12mm to 15mm thick, 600mm x 600mm best quality mineral fibre tiles of approved make fixed on M.S. steel sunners Trume i/c cost of screws angles, cleats, rawel plugs, with taping and painting, etc. complete in all respects as approved by the Engineer-in-charge.		562.966	800.00	
11	16.61	Distempering Finishing walls with exterior decorative cement based paints such as snowcem, Robbiacem etc. on new work, two coats to give an even shade.	Sq.m.	700.935	7.25	