

Detail Notice inviting Tender

Name of work - Proposed Track + Setting Stair

Estimated Cost - Rs. 4330305-00
Earnest Money - Rs. 86606-00

SR. No.	NS/ H.S.R. Item No.	Description	Unite	Quintity	H.S.R. Rate 1988	Contractor Rate
1	1 N.S.	Earth filling (Tibba sand) free from vegetation and sock etc. brought from out side with irrespective of lead from source of earth to site of work including all lead and lift and laying in 15 cm layers including , ramming watering & consolidation solling & compensation of earth taken from private land. The successive layer of earth should not be provided until and unless layer under construction is thoroughly compacted and watered.The complete sate quotation by the contractor shall take in to account all allowances for labour hardness , wetness and all kind of carrige, loading, unloadind, total land and lift of soil involved to the entire satisfaction of Engineer-in-charge confirming fully to specification No. 6.2 &6.3 of Haryana PWD specification 1990 including subsequent agenda and corrigenda issued from time to time (N.S.)	cum	19810.188	-	
2	33.10(ii)	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for moving including supplying good earth if needed.In rows 7.5 cm apart in either direction.	Per 100 Sq.m.	21439.699	40.30	
3	29.55	CONSTRUCTING STANDARD DRAIN TYPE III as per above item No.29.52	RM	606.000	85.00	
4	11.2	Brick Work in Cement Mortar First class brickwork laid in cement sand mortar 1:6 in foundation and plinth.	cum	143.940	393.45	
5	14.23	Brick-on-edge flooring laid in cement sand mortar 1:4 on 75 mm thick cement 1:8:16 and 100 mm sand filling and cement pointed 1:2 on top.	Sq.m.	136.800	85.55	
6	14.54	Rough red sand stone (from Agra) 40 mm thick set in 12 mm thick cement coarse sand mortar in cement coarse sand mortar 1:3	Sq.m.	684.000	86.10	